MYSORE CITY MUNICIPALITY.

NOTICE.

For removal of street rubbish and night-soil in Mysore City for 1910-11.

1. Notice is hereby given that sealed tenders for the exclusive privilege of removing both street rubbish from dust-bins and other collections and of night-soil from private and public latrines, or of each, separately in Mysore City, for eleven months beginning with 1st August 1910 and ending with 30th June 1911, are invited by the President, City Municipality, Mysore.

2. Tenders will be received up to Friday the 15th July 1910 at the Health Office, Mysore.

3. Tenders are to be superscribed "Tenders for the removal of street rubbish and night-soil (or one of them as the tenderer chooses) in the City Municipality, Mysore."

4. No tenders will be received unless accompanied by a deposit of Rs. 100 in cash or currency notes, which will be returned in case of those whose tenders are not accepted.

5. The deposit of the successful competitor will be retained and will be forfeited if he fails to execute the contract bond or infringes its conditions.

6. The contractor must furnish his own bulls, carts and drivers, which should be approved by the Health Officer.

7. The President reserves to himself the right of accepting or rejecting any tender without assigning reasons for doing so.

8. Particulars will be supplied on application to the Health Officer, Mysore City, in person or writing.

V. L. MANKER,
For *President*.

CHITALDRUG DIVISION.

Dated 16th June 1910.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 10th July 1910, for constructing an additional building in the compound of the Anglo-Vernacular School at Chitaldrug. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1911.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing an additional building in the compound of the Anglo-Vernacular School at Chitaldrug," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Constructing a new additional building in the compound of the Anglo-Vernacular School at Chitaldrug.

Item No.	Details of work	Per	Quantity
1	Earthwork, excavation, foundation	C. yd.	145
2	Earthwork, filling in basement	„	208
3	Jelly concrete	C. ft.	1,260
4	Burnt stone in mortar, foundation and basement	„	4,261
5	Burnt stone in mortar, superstructure	„	7,419
6	Burnt stone in mortar, arch-work, cut stone ...	„	117
7	Burnt stone slabs, 6″ thick, roughly dressed	S. ft.	1,299
8	Cut stone pillars with base and capitals nicely dressed ...	No.	6
9	Plastering with mortar	Sqr.	63·47
10	Plastering with chunam	„	46·23
11	Whitewashing	„	63· 7
12	Chiselling and dressing the quoin work at corners ...	R. ft.	288
13	Brick in chunam, parapet wall including cornice, pilasters, etc., complete, 9″ thick, 2½′ high	„	453
14	Thick cornice brick masonry, 12″ thick	„	500
15	Pucka terrace roof, 9″ thick with brick on edge and plastering, etc., complete	Sqr.	20·44
16	Roofing with 1st class Mangalore tiles with teak reepers, etc., complete	„	20·12
17	Ornamental ridge tiles set in mortar	R. ft.	115
18	Rolled steel girders including top and bottom pilasters with revetting, etc.	Cwt.	129
19	Iron trusses, etc., complete, 8′ centre to centre, main hall (18 feet clear span)	No.	7
20	Teakwood work wrought and put up, including wood-oiling ...	C. ft.	490·46
21	Teakwood pannelled doors, complete	S. ft.	300
22	Teakwood windows with ⅓-pannelled and ⅔-glazed shutters with iron bars 1½ feet for light, complete	„	650
23	Teakwood circular glazed ventilators	„	9
24	Teakwood rectangular ventilators with glazed shutters ...	„	72
25	Teakwood cupboards with frames and inside planks and pannelled shutters, etc., complete	„	160
26	Bottom ventilators with expanded metal with teakwood frames, etc., complete	„	100
27	Charlton's silicate painting...	Sqr.	10·09
28	Teakwood partition screen with ¾″ thick plank and frame 1¼″ battons, etc., complete	S. ft.	612
29	Extra cost for Sahash arrangements to lift the screen to a height of 8 feet whenever required with steel wire rope, brass rollers, wheel, etc	L.	S.
30	Providing Mangalore glass tiles	No.	20
31	Zinc sheets with teakwood ½″ plank	R. ft.	115
32	Flooring with 2″ thick Cuddapah slabs over 3″ concrete bed and cement-pointing, etc.	Sqr.	29·38
33	Ornamental masonry finials, big	No.	9
34	Do do small	„	44
35	Ornamental teakwood eave-boards 9″	R. ft.	40
36	Providing rain-water down pipes including fitting... ...	L.	S.
37	Inscription and ornamental work with cornices, etc., for gables	L.	S.
38	Brick masonry gable walls for dormer-windows including plastering, cornice with finials, etc., complete	...	...

The undermentioned materials have been ordered to be collected before June 1910. The contractor whose tender may be accepted must take them and carry out the remaining works:—

1.	Stone slabs, 6″ thick	1433	S. ft.
2.	Do 9″ thick	34	C. ft.
3.	Burnt size stones	22,000	
4.	Stone jelly for concrete	50	C. yds.
5.	Teakwood scantlings	545	C. ft.
6.	Cuddapah slabs, 2″ thick	32·00	Sqrs.
7.	Box-girders	130	Cwt.
8.	Mangalore tiles	2,400	
9.	Glass tiles	20	
10.	Ridge tiles	90	R. ft.

C. KRISHNA IYENGA, *Executive Engineer.*